

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20019-00-01

Spot: NENESWSW

Sec/Twnshp/Rge: 25-16S-27W

1006 feet from S Section Line,

4238 feet from E Section Line

Lease Name: MCBEE C

Well #: 2-25

County: LANE

Total Vertical Depth: 4623 feet

Operator License No.: 9408

Op Name: TRANS PACIFIC OIL CORPORATION

Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	4.5	2178		WITH 285 SX CMT
PROD	4.5	4619	0	WITH 235 SX CMT
SURF	8.625	292		WITH 200 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/23/2017 9:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Revd. from: MONTE BOYDSTON

Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 40 SX CMT & 200# HULLS. PULL TBG TO 2200' & PUMPED CMT TILL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/23/2017 11:45 AM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4115' & PUMPED 20 SX CMT & 200# HULLS. PULL TBG TO 2200' & PUMPED 160 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4253			
4247			
4222			
4159	4162		
4074	4078		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier
SA

(TECHNICIAN)

RECEIVED
OCT 24 2017
KCC DODGE CITY

Form CP-2/3