

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-01499-00-00
Spot: SENEENENW Sec/Twnshp/Rge: 29-25S-14E
500 feet from N Section Line, 2325 feet from W Section Line
Lease Name: MYRTLE CORKERY Well #: 1-B
County: WOODSON Total Vertical Depth: 1425 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1425		20 SX
SURF	7	40		20 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/09/2017 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: JIM THWEATT Company: Phone: (620) 836-2000

Proposed Plugging Method: perf at 550ft and 250 ft 50 ft cement plug at bottom, gel spacer, 50 ft cement plug at 550ft cement from 250ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/09/2017 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1386', pumped 20 sxs cement, pulled tubing to 538', pumped 15 sxs cement, pulled tubing to 250', pumped 60 sxs cement to surface.

Perfs:

RECEIVED
KCC DIST #3
NOV 13 2017
CHANUTE, KS

mt

INVOICED
DEC 18 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern

(TECHNICIAN)

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3648**
Foreman Steve Mearl
Camp Eureka

API 15-207-01499

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-9-17	1000	MYRTLE CORKERY #1-A	29	25S	14E	Woodson	KS
Customer <u>Trimble & Macloskey Oil LLC</u>			Unit #		Driver		Unit #
Mailing Address <u>P.O. Box 171</u>			102		Risks		
City <u>Gridley</u>			110		Jason		
State <u>KS</u>			145		Steve		
Zip Code <u>66852</u>			125		Gregg		

Job Type PIA old well Hole Depth 1450' Slurry Vol. _____ Tubing 2 3/8
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Plug well as follow. Pump 300' Gel Spacer.
Spot 20 SKS AT 1386'
Spot 15 SKS AT 538'
60 SKS 250' to Surface
Total 95 SKS 60/40 Pormix Cement 4% Gel
Job Complete Rig down.

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	25	Mileage	3.95	98.75
C203	95 SKS	60/40 Pormix Cement	12.75	1211.25
C206	325#	4% Gel	.20	65.00
C206	300'	Gel spacer	.20	60.00
C108	4.09 Ton	Ten Mileage bulk Truck	M/C	345.00
C113	2 hrs	Bobbi Val Truck	85.00	255.00
C203		Johnson #28 35 SKS 60/40 Pormix TOP	12.75	446.25
C203		Lane #2 10 SKS 60/40 Pormix OFF	12.75	127.50
590 <18054> #3430.12			Sub Total	3358.75
			Sales Tax	251.91
Authorization <u>by Brian</u> Title <u>Co Rep</u>			Total	3610.66

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.