

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-20911-00-00
Spot: SESWNW Sec/Twnshp/Rge: 22-32S-26W
2982 feet from S Section Line, 877 feet from W Section Line
Lease Name: RANDALL Well #: 22-2
County: MEADE Total Vertical Depth: 5650 feet

Operator License No.: 34531
Op Name: TRIPLE T RESOURCES, LP
Address: 4809 COLE AVE, STE 108
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5568		
PROD	2.875	5650	695	WITH 350 SX CMT
SURF	8.625	972		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/17/2017 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CUT TBG OFF AT TOP OF FISH. LAY TBG DOWN & RUN WORK STRING TO 600'. PUMP 10 SX GEL & 50 SX CMT. REPEAT IF NECESSARY. PULL TO 300' & PUMP 40 SX CMT. PULL TO 60' & PUMP 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2017 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

1 1/4" TBG STUCK IN 2 7/8" PRODUCTION CASING. FISHED FROM 9-7-17 TO 9-11-17. EST. TOP OF FISH AT 601'. LOCATED FISH/SHOT OFF 2 7/8" AT 695'. PULLED TBG OUT OF HOLE TO CHECK CONDITION. RAN TBG TO TOP OF FISH PUMPED 50 SX CMT WITH 3% CC. PULLED OUT OF HOLE. SHUT DOWN FOR 1 1/2 HOURS. TAGGED CMT AT 520'. RAN TBG TO 330' & CIRCULATED CMT TO SURFACE WITH 120 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5455	5480		

INVOICED
DEC 18 2017

Remarks: USED COMMON CMT BY COPELAND CEMENT.

Plugged through: TBG

District: 01

Signed Larry Harris ECRS
(TECHNICIAN)

RECEIVED
OCT 20 2017
KCC DODGE CITY