

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22989-00-00
Spot: SWNW Sec/Twnshp/Rge: 32-20S-25W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: DOEBBELING Well #: 1
County: NESS Total Vertical Depth: 4471 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
DVT		1572		WITH 350 SX CMT
PROD	5.5	4467	0	WITH 150 SX CMT
SURF	8.625	601		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2017 8:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: HUNTER HEMBREE Company: VESS OIL CORPORATION Phone: (785) 798-5151

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT. RUN TBG TO 1600' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIED ONTO BACKSIDE & FILL BACKSIDE WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 10/18/2017 10:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4300' WITH 2 SX CMT. RUN TBG TO 1600' & PUMPED 180 SX CMT. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4354	4360		

INVOICED
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
OCT 24 2017
KCC DODGE CITY