

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-22736-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 11-28S-4E
3880 feet from S Section Line, 1858 feet from E Section Line
Lease Name: AUGUSTA UNIT Well #: 6-56
County: BUTLER Total Vertical Depth: 2675 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1920		
PROD	5.5	2674		250 SX
SURF	8.625	263		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2017 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/24/2017 11:50 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 1744', QES ESTABLISHED CIRCULATION, MIXED AND PUMPED 50 SXS CLASS A COMMON 3% CC AND 40# HULLS & DISPLACED IN CASING. WAITED 2 HOURS. TAGGED CEMENT @ 1550' TESTED CASING, HELD OK. RIH ON WIRELINE, PERFORATED AT 315-316' (4 HOLES). SWEDGED INTO 5 1/2" CASING, QES ESTABLISHED CIRCULATION, MIXED AND PUMPED 140 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #54682.

Perfs:

Top	Bot	Thru	Comments
2610	2612	CSG	
2592	2594	CSG	
2568	2570	CSG	
2556	2560	CSG	
2554	2556	CSG	
2052	2057	CSG	
1743	1749	CSG	

INVOICED
DEC 18 2017

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

JK