

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23232-00-00  
Spot: E2SENE Sec/Twnshp/Rge: 19-34S-11W  
1980 feet from N Section Line, 330 feet from E Section Line  
Lease Name: LOGAN Well #: 6-X  
County: BARBER Total Vertical Depth: 5220 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4600		WITH 2 SX CMT
PROD	4.5	5101	1630	WITH 250 SX CMT
SURF	10.75	246		WITH 200 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/06/2017 1:00 PM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Rcvd. from: LARRY DREILING Company: WOOLSEY OPERATING Phone: (620) 886-5606

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/06/2017 2:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4600' WITH 2 SX CMT ON TOP. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT. TOPPED OFF WITH REDIMIX.

Perfs:

Top	Bot	Thru	Comments
4804	4824		
4768	4782		
4728	4824		

INVOICED  
DEC 18 2017

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
NOV - 9 2017  
KCC DODGE CITY