

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-03987-00-01
Spot: SWSWSESE Sec/Twnshp/Rge: 10-15S-18W
313 feet from S Section Line, 1151 feet from E Section Line
Lease Name: WASINGER Well #: 3
County: ELLIS Total Vertical Depth: 960 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	1175		550 SX

Well Type: SWD UIC Docket No: D08916.0 Date/Time to Plug: 10/31/2017 9:00 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC DBA Phone: (785) 623-0546

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/800 # hulls.
TD was 3638'. 5 1/2" casing was pulled in 1973 - 1974.
CH Perforations: 702' - 860'.
Well was flowing. Previous Operation had packer in hole at 651'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2017 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ultimate Well Service ran in hole with tubing to 650' and hit bridge. Washed down to 700' and circulated cedar hills sand out. Didn't wash tubing down further to avoid sticking tubing. Pumped 175 sx cement w/600 # hulls mixed in to circulate cement up 8 5/8' surface casing. Pulled tubing. Rigged to 8 5/8' surface casing and pumped 10 sx cement w/500 psi. Shut in pressure 500 psi.

GPS: 38.75586 -099.30457

Perfs:

Top	Bot	Thru	Comments
702	860		

INVOICED
11/13/17

Remarks: GLOBAL CEMENTING CO TICKET # 3185

Plugged through: TBG

District: 04

Signed

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

NOV 06 2017

NOV 20 2017
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3