

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-173-20571-00-01
Spot: S2S2SE Sec/Twnshp/Rge: 36-25S-1W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: ROYAL Well #: 1
County: SEDGWICK Total Vertical Depth: 3552 feet

Operator License No.: 34144
Op Name: CAMIO ENTERPRISES, LLC
Address: PO BOX 308
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3510		125 SX
SURF	8.625	245		150 SX

Well Type: EOR UIC Docket No: E26415.1 Date/Time to Plug: 08/09/2017 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: JOHN LACHENMAYR Company: LACHENMAYR OIL Phone: (316) 284-1991

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/10/2017 6:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

PULLED TUBING. RAN BACK IN CASING AND TAGGED BOTTOM AT 3150', DUMP 3 BBLs OF SAND DOWN WELL FOR BOTTOM PLUG AND LET IT SIT OVERNIGHT, RAN BACK IN CASING AND TAGGED TOP OF SAND AT 3002'. PUMPED 60 SX OF COMMON DOWN TUBING FOR BOTTOM PLUG, TAGGED TOP OF BOTTOM PLUG AT 2372'. PERFORATED 5.5" AT 300' AND CIRCULATE CEMENT TO SURFACE WITH A 60/40 POZ-MIX WITH 4% GEL. CAME BACK NEXT DAY AND NO DROP IN TOP PLUG. CUT OFF CASING 3' BELOW SURFACE AND GRADED AREA.

Perfs:

Top	Bot	Thru	Comments
3388	3392	TBG	

Remarks: ELITE CEMENTING & ACID SERVICES. LLC TICKET #3464

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

INVOICED
DEC 10 2017

1/3