

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-01478-00-02
Spot: NESWSWNW Sec/Twnshp/Rge: 32-19S-10W
2988 feet from S Section Line, 4709 feet from E Section Line
Lease Name: CROSS REACH FARMS Well #: 1
County: RICE Total Vertical Depth: 3600 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 3912
SHAWNEE, KS 66203

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3347		Additional Cementing: squeeze at 3158' TO 3162', 3111' TO 3112', 3057' TO 3058', 3040' TO 3041' W/100 sxs; @ 2524' TO 2555' W/50 sxs; @ 1886' TO 1916' W/100 sx and at 627' TO 656' W/ 200 sxs cement.
PKR	5.5	3270		
PROD	5.5	3290		200 SX
SURF	8.625	228		175 SX
T1	2.875	3270		240 SX

Well Type: SWD UIC Docket No: D28014.0 Date/Time to Plug: 11/16/2017 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: DENNIS D HUPFER Company: HUPFER OPERATING INC. Phone: (785) 623-8813

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2017 3:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

WELL HAS HAD NUMEROUS SQUEEZES PERFORMED AT VARIOUS DEPTHS. CASING HAD CORRODED BADLEY ENOUGH FOR TUBING TO DROP DOWN OUT OF TUBING HEAD. TUBING WAS CEMENTED IN. CONNECTED ONTO CASING AND MADE SURE WELL STILL HAD NORMAL VACUUM. STAGED IN 90 SX'S COMMON CEMENT AND LET SET FOR 2 HOURS. CAME BACK AND WAS THOUGHT TO HAVE TAGGED CEMENT AT 75'. CAME BACK AND SLOWLY PUMPED ANOTHER 170 SX'S BEFORE FILLING UP TO THE 5.5" CASING. RUN 1" TUBING ON BACKSIDE TO 288' AND PUMPED APPROX. ANOTHER 130 SX'S TO FILL UP BACKSIDE AND TOP OFF 5.5". PULLED 1" TUBING OUT AND TOPPED OFF WITH APPROX. 5 SX'S. USED TOTAL OF 395 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3290	3600		OH
INVOICED DEC 14 2017			

Remarks: COPELAND TICKET # 45799.

Plugged through: TBG

AK

District: 02

Signed Virgil Clothier
(TECHNICIAN)

Form CP-2/3

INVOICED
DEC 14 2017