

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23421-00-01
Spot: SWNENENE Sec/Twnshp/Rge: 36-16S-22W
4934 feet from S Section Line, 333 feet from E Section Line
Lease Name: SUNLEY Well #: 1-36
County: NESS Total Vertical Depth: 4370 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4190		WITH 2 SX CMT
DVT	5.5	1714		WITH 375 SX CMT
PROD	5.5	3684	0	WITH 410 SX CMT
SURF	8.625	263		WITH 160 SX CMT

Well Type: EOR UIC Docket No: E2767L1 Date/Time to Plug: 10/18/2017 7:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICHARD L SCHREIBER Company: RICHLAN DRILLING Phone: (620) 793-2032

Proposed Plugging Method: SET CIBP @ 4190' WITH 2 SX CMT. RUN TBG TO 1750' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & FILL WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2017 4:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP ALREADY SET AT 4190'. PUT 2 SX CMT ON IT. RAN TBG TO 1750' & PUMPED 150 SX CMT. LOST CIRCULATION. PULLED TBG. TIED ONTO BACKSIDE & PRESSURED UP TO 300# RIGHT AWAY. TIED ONTO BACKSIDE & PUMPED 80 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4239	4241		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED
OCT 24 2017
KCC DODGE CITY

Signed

Michael Maier
514

(TECHNICIAN)

INVOICED
DEC 15 2017