

15.113.04591.0000

Form CP-3  
Rev. 6-26-62

10  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAR 25 1964  
3-25-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Forbes Casing Pulling Co.

Complete Address: P.O.Box 221, Great Bend, Kansas

Lease Name Graber Well No. 5

Location W/2- W/2- SE- Sec. 29 Twp. 21 Rge. 1 (E)/(W)

County McPherson Total Depth 3330'

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Company Tools

Address: same License No. 49

Operation Completed: Hour 11:30AM Day 23 Month 3 Year 64

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3330' back to 3310'. Ran 6 sax cement w/ dump bailer.  
Shot off and pulled 7" casing. Filled hole w/ mud from 3265' back to 180'. Set a 20'  
rock bridge and filled hole w/ ready mix cement from 160' back to zero. 10 3/4"  
surface pipe 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 3/26/64  
INV. NO. 8856-W