

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-22722-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 31-21S-7W
4863 feet from S Section Line, 362 feet from E Section Line
Lease Name: RANDOLPH TRUST 2107 Well #: 31-1
County: RICE Total Vertical Depth: 4675 feet

Operator License No.: 35053
Op Name: TAPSTONE ENERGY, LLC
Address: PO BOX 1608
OKLAHOMA CITY, OK 73101

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|---------------|
| CIBP | 7 | 3841 | | |
| COND | 18 | 62 | | 18 SX CEMENT |
| | 11 | 7 | 3891 | 353 sx cement |
| PKR | | 3841 | | |
| PROD | 7 | 3891 | | 353 SX |
| SURF | 9.875 | 520 | | 375 SX |
| T1 | 4.5 | 3851 | | |

Well Type: SWD UIC Docket No: D31524.0 Date/Time to Plug: 11/06/2017 11:00 AM
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC
Proposal Revd. from: RANDY SUMMERS Company: TAPSTONE ENERGY LLC Phone: (405) 850-6111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 11/06/2017 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL TUBING. SET CIBP AT 3841' AND CAP WITH 7 SX'S CEMENT AND GEL TO SURFACE. RUN CBL TO 1500' THAT INDICATED CEMENT ON BACKSIDE OF 7" CASING. RUN TUBING TO 1050' AND PUMPED 50 SX'S CEMENT. PULLED TUBING OUT AND WAITED AWHILE. TAGGED CEMENT TOP AT 857'. RUN TUBING TO 600' AND CIRCULATED CEMENT TO SURFACE. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3891 | 4675 | OH | |

INVOICED
DEC 18 2017

Remarks: BASIC SERVICES CEMENT TICKET #15498. YELLOW JACKET OILFIELD SERVICES WIRELINE. TA - N.O.V WELL.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)