

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21451-00-00  
Spot: NENESENW Sec/Twnshp/Rge: 20-19S-28W  
3651 feet from S Section Line, 2952 feet from E Section Line  
Lease Name: LENORE Well #: 2  
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2137	0	WITH 450 SX CMT
SURF	8.625	214		WITH 140 SX CMT

Well Type: SWD UIC Docket No: D25317.0 Date/Time to Plug: 10/24/2017 10:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: MONTE BOYDSTON Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: RUN TBG TO 1700' & CIRCULATE CMT TO SURFACE WITH CMT & 400 TO 500# HULLS. TOOH WITH TBG. TOP OFF CASING. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: HEITH WALSH Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/24/2017 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RUN TBG TO 1700'. CIRCULATE CMT TO SURFACE WITH 170 SX CMT & 200# HULLS. TOP OFF WITH 10 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS. PRESSURE TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
1750	1850		


INVOICED  
DEC 18 2017

Remarks: USED60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

  
SIA

(TECHNICIAN)

RECEIVED  
OCT 31 2017  
KCC DODGE CITY