

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01254-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 13-30S-9W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: NICHOLAS A Well Number: SWD
County: KINGMAN Total Vertical Depth: 4295 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

Conductor Pipe: Size feet: 139.59
Surface Casing: Size 8.625 feet: 408 275 SX CMT
Production: Size 4.5 feet: 4054 275 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D12180.0 Date/Time to Plug: 08/15/2002 8:00 AM
Plug Co. License No.: 5042 Plug Co. Name: EDMISTON OIL COMPANY, INC.
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL COMPANY, INC. Phone: (620) 792-6924

Proposed Plugging Method: Sand to 3,420' and top with 5 sxs. cement. Perforate 2 7/8" tubing and 4 1/2" casing at 1,400', 925', and 460'. Run tubing to 1,400' and spot 35 sxs. cement. Pull tubing to 925' and spot 35 sxs. cement, Pull tubing to 460' and circulate cement to the surface.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/16/2002 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Ran 1" tubing to 3397' and spotted 10 sxs. cement. Pulled 1" tubing. Perforated 2 7/8" & 4 1/2" at 1,400'. Ran 1" tubing to 1,351' and spotted 35 sxs. cement. Pulled 1" tubing. Perforated 2 7/8" & 4 1/2" at 925'. Ran 1" tubing 905' and spotted 35 sxs. cement. Pulled 1" tubing. Perforated 2 7/8" & 4 1/2" at 460'. Ran 1" tubing to 421' and tried to circulate 195 sxs. cement (no CaCl) to the surface. Cement did not circulate - let cement set. Ran wireline inside 2 7/8" to 230'. Ran wireline outside 4 1/2" to 745'. Ran 1" tubing on outside of 4 1/2" and circulated 105 sxs. cement to the surface, Ran 1" inside 2 7/8" to 217' and circulated 10 sxs. cement to the surface.

RECEIVED
KCC DISTRICT #2

AUG 19 2002
8-19-02
WICHITA, KS

Remarks: USED 380 SXS COMMON W/3% CALCIUM CHLORIDE BY ALLIED CEMENTING. INVOICE #10129 & 10130.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE

8-22-02

INV. NO.

2003060334