

2 040370

10-20-87

API NUMBER 13- 095-30,026 A .00.01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SW, SEC. 31, T 30 S, R 9 W/EX

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Robinson & K Well # 2

Operator: Vincent Oil Corporation

County Kingman 144.95

Name:

Address 125 N. Market

Well Total Depth 4460 PBD 4435 feet

Wichita, KS 67202

Conductor Pipe: Size 4 1/2" feet 4487

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:30am Day: 20 Month: 10 Year: 19 87

Plugging proposal received from Elmo

(company name) Clarke Corporation (phone) _____

work: Sand back to 4310 and dump 4 sxs cement with dump bailer. Pull casing.

Squeeze top by pumping 3 sxs hulls, 10 sxs gel, 100 sxs 60/40 pozmix into 8 5/8"

surface pipe

Plugging Proposal Received by Glenn L. Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:30 Day: 20 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT Sand was dumped down 4 1/2" to 4310 and capped with 4 sxs cement. The

4 1/2" was shot off and recovered from 2800'. The top was squeeze plugged by

pumping 300# hulls, 10 sxs gel and 100 sxs of 60/40 poz into 8 5/8" surface pipe.

Remarks: B.J. Titan #388960 Max 500# Shut-in 350#

(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
I (and my employees) hereby observe this plugging.

DATE 10-22-87 OCT 21 1987 10-21-87 Signed _____
(TECHNICIAN)

INV. NO. 18626 CONSERVATION DIVISION
Wichita, Kansas