

7-22

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-095-21,580.00.00
C W/2 SE SW, SECTION 16 TOWNSHIP 30 RANGE 9W

OPERATOR LICENSE # 6581 1320 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR BISON ENERGY CORP
NAME & 9320 EAST CENTRAL
ADDRESS WICHITA KS 67206

LEASE NAME: HAWLEY 1-16
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4421' 143.68

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 213'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: JEFF CAPPS
COMPANY NAME: SHAWNEE WELL SERVICE PHONE: _____

WERE: 5-1/2" @ 4419' - PERFS 4322'-4421' - SAND TO 4260' & 5
SX - 30 SX @ 1400' - 30 SX @ 900' - CIRC FROM 260'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 1900 DAY: 22 MONTH: 7 YEAR: 1993

ACTUAL PLUGGING REPORT:
PERFS COVERED WITH SAND TO 4260' & CAPPED WITH 5 SX
CMT - 5-1/2" RECOVERED FROM 2793' & PULLED TO 1432' &
30 SX CMT SPOTTED - 5-1/2" PULLED TO 975' & 30 SX CMT
SPOTTED - 5-1/2" PULLED TO 260' & CMT CIRC TO SURF
RECOVERED CASING PULLED FROM WELLBORE & CMT FILLED TO
SURFACE.

REMARKS: ALLIED #5885 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 10-13-93
INV. NO. 38930

[Signature]

Steve Van Gieson (AGENT)

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1993
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90