

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

10-3

API NUMBER: 15-095-20,921,00.00

5/2 SE, SECTION 13 TOWNSHIP 30 RANGE 9W

OPERATOR LICENSE # 5042 330 FEET FROM S SECTION LINE
OPERATOR EDMISTON OIL COMPANY INC 1320 FEET FROM E SECTION LINE
NAME & 125 N. MARKET, SUITE 1310
ADDRESS WICHITA, KS 67202

LEASE NAME: NICHOLAS "A" #3
COUNTY: KINGMAN 139.78
WELL TOTAL DEPTH: 4301'
PIPE: 4 1/2" @ 4300'
SURFACE CASING: 8 5/8" @ 326'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 3 MONTH: 10 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MANNY
COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943
WERE: SAND TO 4190' AND 4 SACKS
35 SACKS AT 1375'
35 SACKS AT 925'
375' TO 0'

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 07 1996

PLUGGING PROPOSAL RECEIVED BY: M.W.

CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 3 MONTH: 10 YEAR: 1996


ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 4160' AND 4 SACKS. 4 1/2" CASING PARTED AT 1600, PULLED TO 1375', PUMPED 35 SACKS. PULLED TO 925' AND PUMPED 35 SACKS. PULLED TO 375' AND CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #7249

INVOICED

DATE 10-9-96
INV. NO. 46663

I DID OBSERVE THIS PLUGGING.


JACK L. LUTHI

10-7-96