

To: 1 070147
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21, ~~659~~ ^{351.00.00}
SW SE NE, SEC. 13, T 16 S, R 20 (W/XX)
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5252
Operator: R. P. Nixon
Name & Address: 207 W. 125th
Hays, KS 67601

Lease Name Elmore Well # 4
County Rush
Well Total Depth 3897 ^{126.65} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1093

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor R. P. Nixon License Number 5252

Address 207 W. 125th, Hays, KS 67601

Company to plug at: Hour: 3:00 pm Day: 6 Month: March Year: 19 86

Plugging proposal received from Paul Nixon

(company name) R. P. Nixon (phone) 913-628-3834

were: 4 1/2" at 3944' PBD 3912' Perfs at 3505-3894'
1st plug sand back to 3470' and dump 2 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 20 sx gel, 50 sx cement, 5 sx gel, 1/2 sack hulls
and 125 sx cement.

Plugging Proposal Received by Don Ubel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 pm Day: 6 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3470' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 20 sx cement, 50 sx cement,
5 sx gel, 1/2 sack hulls, and 125 sx cement.

Maximum pressure 600 psi and shut in 400 psi

Remarks: Recovered 2600' 4 1/2 " casing. Used 60/40 Pozmix 6% gel 2% cc by BJ-Titan.
(If additional description is necessary, use BACK of this form.)

INVOLCED

DATE MAR 10 1986

STATE CORPORATION COMMISSION Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 12885

3-6 APR 10 1986

MAR 10 1986 3-10-86

CONSERVATION DIVISION