

To: 1 071123
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-3

API NUMBER 15- 8/82 15.165.30131.00.01
SE NW SE, SEC. 12, T 16 S, R 16 W/EX
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3763
Operator: Paramount Ent.
Name & Address: P.O. Box 861
Hays, KS 67601

Lease Name Bergann Well # 1
County Rush
Well Total Depth 3650 118.63 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 997

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Paramount Ent. License Number 3763
Address P.O. Box 861, Hays, KS 67601

Company to plug at: Hour: 9:30 a.m. Day: 3 Month: 11 Year: 19 92

Plugging proposal received from Ron Geist
(company name) Paramount Ent. (phone) 913-628-1099

Work: 5 1/2" at 3593' w/200 sx cement, PBSD 3543', Perfs at 3216-3500'
1st plug sand back to 3166' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 200 lbs. hulls and 200 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 a.m. Day: 3 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3166' and dumped 5 sx cement on top of sand through bailer,
2nd plug pumped 200 lbs. hulls and 200 sx cement down 8 5/8".
Maximum pressure 900 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. Recovered 2693' of 5 1/2" casing.
If additional description is necessary, use BACK of this form.

INVOICED

I (did / did not) observe this plugging.

DATE 12-8-92

INV. NO. 37011

Signed Dan Johnson (TECHNICIAN)

11-3-92 JAN 22 1993