

To: 1 060064

10-23 API NUMBER 15-165-21,665.00.00

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

W/2 W/2 NW, SEC. 31, T 19 S, R 20 W/EX

3960 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5228

Lease Name Young Well # 1-31

Operator: Parrish Corporation

County Rush 144.53

Name & Address 110 S. Main, Ste. 510

Well Total Depth 4447 feet

Wichita, KS 67202-3745

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 483

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 23 Month: 10 Year: 1997

Plugging proposal received from James Ray

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

core: 5 1/2" at 4418'. Open hole 4418-4447'

1st plug 1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer,

2nd plug at 1450' with 50 sx cement, 3rd plug at 40' with 700 sx cement,

4th plug at 500' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4 p.m. Day: 23 Month: 10 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 5 sx cement on top of sand through bailer.

2nd plug at 1400' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 500' with 50 sx cement,

5th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 2800' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE: OCT 20 1997

Signed Michael Mauer (TECHNICIAN)

INV. NO. 49378