

1 070950

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-165-20,776 . 00.00
150' E of
N/2 NE SW, SEC. 31, T. 19 S, R 20 W/E

2310 feet from S section line

3150 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228

Lease Name Schadel Well # 1

Operator: Parrish Corporation

County Rush 142.51

Name & Address P.O. Box 221

Well Total Depth 4385 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:45 a.m. Day: 20 Month: 5 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4366' w/200 sx cement, Open hole 4366-85'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 125 sx cement down 5 1/2",

3rd plug pump 145 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 20 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 125 sx cement down 5 1/2", cement circulated, pulled casing,

3rd plug pumped 145 sx cement down 8 5/8".

Maximum pressure 500 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 475' of 5 1/2" casing, casing parted.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if additional description is necessary, use BACK of this form.) observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 6-18-91

INV. NO. 32166