

1 090470

9-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,575.00.00
C NE NE, SEC. 31, T 19 S, R 20 W/EX
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228

Lease Name Hamzy Well # 1

Operator: Parrish Corporation

County Rush

Name & Address
100 S. Market, Ste. 200
Wichita, KS 67202-3802

Well Total Depth 4400 143.00 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 12 Month: 9 Year: 1994

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4391' w/175 sx cement, Open hole 4391-4400'

1st plug set CIBP at 3350' with 2 sx cement on top,

2nd plug perforate casing at 750', pump in 150 sx cement,

3rd plug hook onto backside and pump in 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 12 Month: 9 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3350' with 2 sx cement on top,

2nd plug perforated casing at 750' and pumped in 150 sx cement,

3rd plug hooked onto backside and pumped in 100 sx cement.

Maximum pressure 500 psi and shut in 500 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. SEP 16 1994

INVOICED

(If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 10-10-94

Signed _____ (TECHNICIAN)

WV. NO. 41372