

To: 1 120856 11-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-20,143-0000
150' NE of
NW SW, SEC. 29, T 19 S, R 20 W/SE
2034 feet from S section line
4514 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Dehner "A" Well # 1
County Rush
Well Total Depth 4358 141.6 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9 a.m. Day: 3 Month: 11 Year: 1993

Plugging proposal received from Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4353' w/175 sx cement, Perfs at 4279-85', Open hole 4353-58'
1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 1480', 3rd plug pump 80 sx cement at 750',
4th plug pump 50' sx cement at 300', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12 p.m. Day: 3 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4200' and dumped 5 sx cement on top of sand through bailer,
2nd plug shot 5 1/2" casing at 715' and pumped 5 1/2" casing volume plus 50 sx cement. Shut in at 100# for one hour.
3rd plug shot casing at 370' and squeezed 40 sx cement through shot hole at 370' at 250#. 4th plug squeezed 8 5/8" X 5 1/2" annulus with 75 sx cement. Shut in pressure 550#.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
Additional description is necessary, use BACK of this form.

INVOICED
NOV 22 1993
DATE 11-22-93
INV. NO. 39283

Signed Devin Rankin 11-12-93
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS