

To: 1 031175
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-22
API NUMBER 15- 165-21,587.00.00 131p
NE NW, SEC. 23, T 19, S, R 20 W&E
4620 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7344
Operator: Clyde M. Becker
Name & Address 212 First National Bldg.
Ponca City, OK 74601

Lease Name Lamer Well # 1
County Rush 141.37
Well Total Depth 4350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling License Number 5929

Address 310 W. Central, Suite 117, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 22 Month: 9 Year: 19 91

Plugging proposal received from Jay Snider

(company name) Duke Drilling (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1430-60'
1st plug at 1440' with 50 sx cement, 2nd plug at 740' with 80 sx cement,
3rd plug at 330' with 40 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None RECEIVED

Operations Completed: Hour: 4:15 a.m. Day: 22 Month: 9 Year: 19 91 COMMISSION

ACTUAL PLUGGING REPORT 1st plug at 1440' with 50 sx cement,
2nd plug at 740' with 80 sx cement,
3rd plug at 330' with 40 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.
SEP 25 1991
9-25-91

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED (Check) (do not) observe this plugging.

DATE 9-27-91
INV. NO. 33238

Signed Steve Durrant
(TECHNICIAN)

FORM MUST BE TYPED
FORM C-1 4/90

EFFECTIVE DATE: 9-16-91

State of Kansas

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL 165-21,587-00-00

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date September 14 1991
month day year

E/2 NE NW Sec 23 Twp 19 S, Rg 20 X East West

4620 feet from South line of Section
2970 feet from East line of Section

(Note: Locate well on Section Plat on Reverse Side)

OPERATOR: License # 07344
Name: Clyde M. Becker
Address: 212 First National Bldg.
City/State/Zip: Ponca City, OK, 74601
Contact Person: Clyde M. Becker
Phone: 405-765-8788

County: Rush
Lease Name: Lamer Well #: 1
Field Name: Flavius South

CONTRACTOR: License # 05929
Name: DUKE DRILLING

Is this a Prorated Field? yes X no
Target Formation(s): Mississippian

Well Drilled For: Well Class: Type Equipment:
X Oil ... Inj ... Infield X Mud Rotary
... Gas ... Storage X Pool Ext. ... Air Rotary
... OWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

Nearest lease or unit boundary: 330
Ground Surface Elevation: 2200' est. feet MSL
Domestic well within 330 feet: yes X no

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Municipal well within one mile: yes X no
Depth to bottom of fresh water: 380
Depth to bottom of usable water: 650

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 300
Length of Conductor pipe required: 0

Projected Total Depth: 4350
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
..... well farm pond other

Exp. 3/11/92

AFFIDAVIT

200' Alt. II Rec. RECEIVED
STATE OF KANSAS COMMISSION
SEP 25 1991

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-1101 et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Jay Snider
SPUD DATE 9-16-91 INIT. R.C.
LENGTH SURFACE PLANNED 300
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8 @ 308 CONDUCTOR
ANHYDRITE T- 1430 B- 1460 - ELEVATION
TD 4350 FORMATION MISS
RAN PIPE @ DV TOOL ALT II DONE
..... SX Y N
..... Arbuckle Plug @ Ft. W/ SX
..... Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 1440 Ft. W/ 50 SX
..... 1/2 Base Anyh. @ Ft. W/ SX
2 1/2, 1/2 Plug @ 740 Ft. W/ 80 SX Flow Seal
3 Bottom Surface @ 330 Ft. W/ 46 SX
4 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE 10 SX
WATER WELL SX Arr. Well Pond X
TECHNICIAN SD DATE 9-19-91 Hauling
TYPE OF CEMENT 60/40 Poe 60% gal.
STARTING TIME 1:30 (AM/PM) DATE 9-22-91
COMPLETION TIME 4:15 (AM/PM) DATE 9-22-91
CEMENT COMPANY Halibenton