

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165 -21,215 . 00. 00

NW SE NE , Sec. 23 , T 19 S, R 20 W/~~E~~

1650 feet from N/~~S~~ section line

990 feet from ~~N~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040

Lease Name Foos Well # 4

Operator: Bankoff Oil Co.

County Rush

Name & Box 700657

Address Tulsa, OK 74170

Well Total Depth 3709 feet 120.54

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Lobo Drilling License Number 5864

Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 6:00 am Day: 11 Month: June Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Ervin Neighbors

(company name) Lobo (phone) 316-692-7476

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1395' with 50 sx cement

2nd plug at 713' with 60 sx cement

3rd plug at 372' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Signed *Glynn Wiley*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:15 am Day: 11 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1395' with 50 sx cement, 2nd plug at 713' with 60
sx cement, 3rd plug at 372' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole
with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

CONSERVATION DIVISION
Wichita, Kansas

6-14-84

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed *Glynn Wiley*
(TECHNICIAN)

INVOICED

DATE 6-21-84

INV. NO. 2089

6-11