

1 070117

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,164A .00.01

NE SE NW

150'N, SEC. 23, T 19 S, R 20
3780 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151

Lease Name Lamer Well # 1-23

Operator: Gear Petroleum Co., Inc.

County Rush 142.58

Name & Address 300 Sutton Place

Well Total Depth 4387 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 556

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 am Day: 2 Month: January Year: 19 86

Plugging proposal received from Danny Kilgore

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4377' PBTD 4330' Perfs at 4318-28'

1st plug sand back to 4270' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:45 pm Day: 2 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 60 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 600 psi and shut in 300 psi

Remarks: Recovered 2700' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986
INV. NO. 12055

RECEIVED
STATE CORPORATION COMMISSION

Signed Dan Gooden
(TECHNICIAN)

JAN 13 1986

CONSERVATION DIVISION
Wichita Kansas