

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,164.00.00

165' E of SE NW 1/4 Sec. 23, T 19 S, R 20 W 10

1980 feet from N/W section line

2145 feet from W/W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5842

Lease Name Lamen Well # 1

Operator: Gabbert-Jones, Inc. et al  
Name & Address 830 Sutton Place  
Wichita, Kansas  
67202

County Reush

Well Total Depth 4385 feet 142.51

Conductor Pipe: Size        feet

Surface Casing: Size 8 7/8" feet 556

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A   ✓  

Other well as hereinafter indicated       

Plugging Contractor Gabbert-Jones, Inc. et al License Number 5842

Address 830 Sutton Place, Wichita, Kansas 67202

Company to plug at: Hour: 3:00 AM Day: 14 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Don Powell

(company name) Gabbert-Jones Inc. et al (phone)       

were: 1st plug @ 1410' w/ 50 lb cement.

2nd plug @ 600' w/ 50 lb cement.

3rd plug @ 40' to 0' w/ 10 lb cement on solid bridge

circulate 15 lb cement in rat hole.

Allied cementing pumped 60/40 prop w/ 27 gal 3% Cc

Cement. Signed Paul A. Luthie

(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None   ✓  

Operations Completed: Hour: 5:15 AM Day: 14 Month: 1 Year: 1984

ACTUAL PLUGGING REPORT 1st plug

filled hole w/ heavy mud & pumped 50 lb

cement through drill pipe to 1410'. 2nd plug with hole full of heavy

mud spotted 50 lb cement through drill pipe @ 600'. 3rd plug filled

hole to 40' & dumped 10 lb sulfox on top of mud & pushed rubber plug to

40' on solid bridge & pumped 10 lb cement filling hole to 0' w/ cement.

circulated 15 lb cement through drill pipe in rat hole.

Remarks: Allied cementing accomplished the plugging.

I hereby certify that the above plugging instructions were given as herein stated and that I ~~was~~ / did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION

Signed Paul A. Luthie (TECHNICIAN)

1-18-84

JAN 18 1984

INVOICED

DATE 1-20-84

FORM CP-2/3 Rev. 9-82

CONSERVATION DIVISION Wichita, Kansas

INV. NO. 9204 IN