

1 020181

9-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-067-20,815.00.00
Approx. C NE, SEC. 6, T 30 S, R 36 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4824

4051 feet from S section line

1265 feet from E section line

Operator: Mesa Operating Limited Partnership

Lease Name McClaren Well # 3-6

Name & Address P.O. Box 2009

County Grant 95.55

Well Total Depth 2940 feet

Amarillo, TX 79189

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 696

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D & S License Number _____

Address _____

Company to plug at: Hour: 3 p.m. Day: 21 Month: 9 Year: 1988

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 5 1/2" at 2940' No perms TOC est. 400' in 5 1/2" & 8 5/8"

Pipe was split at 670' when cemented in. Fluid level 600'. Tagged bottom at 676'.

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1988 9-28-88

Plugging Proposal Received by _____

CONSERVATION DIVISION
Wichita, Kansas

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 23 Month: 9 Year: 1988

ACTUAL PLUGGING REPORT 1st plug pumped 275 sx down 5 1/2", circulated cement out 8 5/8"

annulus. Rigged down, cement dropped in 5 1/2" & 8 5/8" to est. depth of 400-425'. 9/21/88

9/23/88 Cut off 5 1/2" & 8 5/8" four feet below ground level and filled to surface

with Redi Mix.

Remarks: Used Class H cement with 3% cc by D & S. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 10-6-88

Signed Glen R. Barlow
(TECHNICIAN)

INV. NO. 22528