

5 060078

APR 2 1 1987

422
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-22,004.0000

NW NE NW, SEC. 4, T. 21 S, R. 8 W/E

4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4338

Lease Name PEARSON ESTATE Well # 1

Operator: L & G Oil Co.

County Rice 116.116

Name & Address Route 2, Lake Road

Well Total Depth 3574 feet

Pratt, Kansas 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 204-150 sx

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor L & G Oil Co. License Number 4338

Address Route 2, Lake Road, Pratt, Kansas 67124

Company to plug at: Hour: Day: 20 Month: March Year: 19 87

Plugging proposal received from Larry Belding

(company name) L & G Oil Co. (phone) 316 672-6701

were: Do not pull pipe. 100 sx cement between 8 5/8" x 4 1/2". Pump 100 sx to fill casing.

Plugging Proposal Received by Merlan Unruh (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:00 a.m. Day: 21 Month: March Year: 19 87

ACTUAL PLUGGING REPORT 4 1/2" casing not pulled. 100 sx ATL 65/35 poz, 10% gel, 2% diacell between 8 5/8" and 4 1/2". Pumped 100 sx of same to fill casing.

Perf. 3068' - 3072'. Left in hole 3559' of 4 1/2".

Remarks: (if additional description is necessary, use BACK of this form.)

NOTICED

DATE 4-15-87

INV. NO. 16538

RECEIVED

APR 14 1987

MAY 1 4 1987

Signed R. Phil Worley (TECHNICIAN)

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84