

5020320

JAN 22 1987

15.159.00318.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 9-13-57
NW 28, SEC. 28, T. 21 S, R. 7 (W) E
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7883
Operator: Carl Allam Oil Company
Name & Address Box 471
Haven, Kansas 67543

Lease Name Stucky Well # 2
County Rice 110.66
Well Total Depth 3405 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 216-200SK

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, Ks 67524

Company to plug at: Hour: 10:00 AM Day: 22 Month: January Year: 1987

Plugging proposal received from Mark McCabe
(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3335' and cement with 5 sacks cement.
Squeeze hole with 5 sacks hulls, 20 sacks Bentonite, 8 5/8" plug, and
100 sacks 60/40 Pozmix w/ 6% gel. Pump into 8 5/8" surface casing.

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 AM Day: 22 Month: January Year: 1987

ACTUAL PLUGGING REPORT Hole Filled with sand to 3335 and cemented with
5 sacks cement. Hole squeezed with 5 sacks hulls, 20 sacks Bentonite,
8 5/8" plug, and 100 sacks 60/40 Pozmix w/ 6% gel pumped into 8 5/8"
Surface casing.

JAN 30 1987

5 1/2" - 3388' - 75 sacks Recovered 2800' of 5 1/2" casing Max Pressure 500 PSIG

Remarks: close in Press. 100 PSIG. Allied Cementing Co. Inc. # 1557
(If additional description is necessary, use BACK of this form.)

INVOICED

(If you did not observe this plugging:

DATE 2-2-87
INV. NO. 16038

Signed [Signature]
(TECHNICIAN)