

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 8 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Oil Producers, Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Russell, Ks.

Lease Name: Young "B" Well No. 1

Location: NW SW Sec. 9 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4400' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Weiler was instructed to plug the well as follows:  
 Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
 70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
 displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
 plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plug rat hole with  
 2 sk cmt.

Very truly yours,

Geo F. Messersmith  
Conservation Division Agent