



15.165.20601.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1976

CONSERVATION DIVISION
Wichita, Kansas

10-26-76

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Swope of Phillips Petro. has this
date requested permission to plug the following described well:

Mr. Swope guarantees payment of the plugging fee.

Operator's full Name: Phillips Petro., Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name: Bellport "AB" Well No. 2

Location: 150' N of C W/2 NE/4 Sec. 9 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4241' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Swope was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 35 sk cmt plug at 4241' thru drill
pipe. Heavy mud to 550' set 65 sk cmt plug thru drill pipe. Heavy mud
to 250' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent