



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 30 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 24, 1968

12-30-68

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. George Starbuck of Pheonix Drilling Corporation has this date requested permission to plug the following described well:

Mr. Starbuck guarantees payment of the plugging fee.

Operator's full Name: Pheonix Drilling Corporation

Complete Address: 416 Union Center, Wichita, Kansas 67202

Lease Name: Ross Well No. 1

Location: NW NW SW Sec. 4 Twp. 21 Rge. 9 (E)(W)

County: Rice Total Depth 2983' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. George Starbuck was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to 235' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Conservation Division Agent