

State of Kansas



15.159.06632.0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1968

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

November 19, 1968

11-26-68

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Schonoff of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbel

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name: V. A. Martin Well No. 2

Location: NW NE Sec. 35 Twp. 21 Rge. 8 XX (E) (W) X

County: Rice Total Depth 3465' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:

Fill hole with sand to 3340' and cement with 3 sacks.

Fill hole with mud to 260'. Set rock bridge from 260' to 250' and cement
hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge
from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent