

State of Kansas



15.113.04580.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1967
CONSERVATION DIVISION
WICHITA, KANSAS

3-6-67

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Adamson of Continental Oil Co. has this

date requested permission to plug the following described well:

Mr. Adamson guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Co.

Complete Address: Box 267 Great Bend, Kansas

Lease Name: J.C. Goering Well No. # 4

Location: SE SW SW Sec. 29 Twp. 21 Rge. 1 (E) (W)

County McPherson Total Depth 3273' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Adamson was instructed to plug the well as follows:

13"-155'-Cemented. 7"-3252'-Cemented. Top Performance-2396'.
Sand hole to 2321'. 7 Sax. cement 2321' to 2300'. Mud 2300' to 180'.
Bridge 180' to 160'. Cement 160' to 0.

Very truly yours,

J. P. Roberts
Conservation Division Agent