

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-113.04595.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

January 13, 1966
RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1966

CONSERVATION DIVISION
WICHITA, KANSAS

1-18-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. W. E. Adamson of Continental Oil Company has this

date requested permission to plug the following described well:

Mr. Adamson guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company

Complete Address: Box 267, Great Bend, Kansas

Lease Name: F. A. Hetzke Well No. 4

Location: NE NE NE Sec. 29 Twp. 21 Rge. 1 (E) (W) X


County Mc Pherson Total Depth 3319' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Adamson was instructed to plug the well as follows:

Tubing in hole at approx. 360'. Set rock bridge from 360'
to 350' (in 7" casing). Circulate cement from 350' to base
of cellar through 1" tubing. Circulate cement to base of
cellar between 7" casing and 13" surface pipe, pump through
1" tubing.

Very truly yours,


Conservation Division Agent