



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 19, 1964 RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION
Wichita, Kansas

5-25-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling Inc. has this
date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Forbes Casing Pulling Inc.

Complete Address: Box 221, Great Bend, Kansas

Lease Name: J. C. Goering Well No. 11

Location: C NW NW ^{SW} NW Sec. 29 Twp. 21 Rge. 1 Q4 (W) X

County McPherson Total Depth 3325' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

Fill hole with sand to 3200' and cement with 5 sacks.

Fill hole with mud to 165'. Set rock bridge from 165'
to 150' and cement hole to bottom of cellar with 5 yards
ready mix cement.

Very truly yours,

Conservation Division Agent