

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1966
9-13-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name Lebsack Well No. 1

Location SE NW SE Sec. 12 Twp. 16 Rge. 16 (E) (W) X

County Rush Total Depth 3500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 5:30 A Day 9 Month 9 Year 1966

The Above well was plugged as follows:

RTD 3500' 8 5/8 csg set at 995' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 420' and displaced

30 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc

hulls and 10 sc cement to base of celler. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messig
Well Plugging Supervisor

DATE 9-12-66

INV. NO. 3897-W