

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1969
CONSERVATION DIVISION
Wichita, Kansas

3-14-69

Operator's Full Name Pubco Petroleum Corp.,

Complete Address: Box 567 McCook, Nebraska

Lease Name Hamzy Well No. 31-8

Location 150' S of C SE NE Sec. 31 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4490

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 2:15P Day 11 Month 3 Year 1969

The Above well was plugged as follows:

RTD 4490' 8 5/8 csg set at 376' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo J. Muesy
Well Plugging Supervisor

INVOICED

DATE 3/14/69
INV. NO. 9460-u