

*Y*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
9-16-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Building Russell, Kansas 67665

Lease Name Young "A" Well No. 1

Location SW NW Sec. 31 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4410

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 3P Day 13 Month 8 Year 1969

The above well was plugged as follows:

Total Depth 4410' 8 5/8 csg set at 252' cwc

5 1/2 csg set at 4400' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (4380-4412) Dumped 5 sk cmt W/dump bailer. (4340-4412)

Cutoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 12 sk gel W/2 sk hulls, plug and 130 sk

50-50 poz cmt 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/16/69

INV. NO. 479-w

Signed: Leo F. Mearns  
Well Plugging Supervisor