

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11-4-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Woodman - Iannitti

Complete Address: 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Pascoe Well No. 1

Location G NE SW Sec. 23 Twp. 19 Rge. 20 (E) (W) XX

County Rush Total Depth 4375

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 3:30P Day 30 Month 10 Year 1968

The Above well was plugged as follows:

RTD 4375' 8 5/8 csg set at 188' cwc. Cement Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cmt thru drill pipe. Heavy mud to 180' set cementing plug at 180' set cementing plug and displaced 20 sc cement. Heavy mud to 140' set cementing plug, 1/2 sc hulls and 10 sc cmt to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/4/68  
INV. NO. 8752-11

Signed: Rio J. Quassey  
Well Plugging Supervisor