

PK
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUL 12 1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION

7-2-75

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Natl. Bldg., Wichita, Kansas

Lease Name Murphy "E" Well No. 1

Location NW SW SE Sec. 12 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4261'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10:30 P Day 28 Month 6 Year 1975

The above well was plugged as follows:

RTD 4261' 8 5/8 csg set 204' cwc 160 sk. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/3/75
INV. NO. 1571-w