

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION
Wichita, Kansas

4-22-64

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shields Oil Producers
Complete Address: Russell, Kansas
Lease Name Young Well No. C-1
Location SW SE SE Sec. 9 Twp. 19 Rge. (E) (W) 20
County Rush Total Depth 4310
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Barnes & Sons & Halliburton Co
Address: Russell, Kansas License No. 9
Operation Completed: Hour 6PM Day 16 Month 4 Year 64

The Above well, was plugged as follows:

8 5/8" .90' circulated with cement - 5 1/2" 4306' with 100 sax cement -
Perf 4210'

Sand back to 4190 4190', set 4 sax cement with dump bailer - pulled
3545' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" - displaced
20 sax cement through 5 1/2" at 470' - heavy mud to 175' - displaced 20 sax
cement through 5 1/2" at 175', gel mud to 40' - set 10 sax cement - cement
went down to 50' - filled with heavy chunk mud 50' to 20', cement 20' to
0' -

Mudding and cementing by Halliburton Co.

I hereby certify that ~~the above well was~~ plugged as herein stated.

INVOICED

DATE 4/23/64
INV. NO. 9003-11

Signed: Edwin Petty
Well Plugging Supervisor