

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1969
CONSERVATION DIVISION
Wichita, Kansas

8-8-69

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Russell, Kansas

Lease Name Young "B" Well No. 1

Location NW SW Sec. 9 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereinafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8P Day 4 Month 8 Year 1969

The above well was plugged as follows:

RTD 4400' 8 5/8 csg set at 250' cwc Cmt. Lat. 50-50 poz cmt W/6% total gal.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plug rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/8/69

INV. NO. 263-W

Signed: Leo J. Nassif
Well Plugging Supervisor