

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1965
3-12-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers

Complete Address: Shields Bldg Russell, Kans

Lease Name Young Well No. C-2

Location SE SE SE Sec. 9 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4319

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons & Halliburton Co

Address: Russell, Kans License No. 9

Operation Completed: Hour 4PM Day 9 Month 3 Year 65

The Above well was plugged as follows:

8 5/8" 255' circulated with cement - 5 1/2" 4319' with 125 sax cement
PB to 4284' Perf 4217'

Sand to 4200', set 4 sax cement with dump bailer - pulled 3020' 5 1/2" to
550', circulated hole with heavy gel mud through 5 1/2" at 550', displaced
20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced 20 sax
cement through 5 1/2" at 200', heavy mud to 35', set 10 sax cement to bottom
cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Perry
Well Plugging Supervisor

DATE 3/12/65

INV. NO. 804-W