

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 6-3

LOCATION SE-SW-NW

SEC. 26 TWP. 19 RGE. 16W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Dirks

Operator Magnolia Petroleum Co. Address 90 C.G. Hill
Box 770 Great Bend Kans.

Field _____ County Rush

Total Depth 3749 Feet.

Plugging Contractor Forbes Casing Pulling Co.

Plugging Contractor's License No. 49

Address Great Bend Kansas

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8" (1) 112.5' l.w.c. Oil string 6 5/8" (1) 3750'
w/ 200 SX Cem. Top Perf 3700'. Fill back with
Chat and Cem to 3695' by Cable tools. 5 SX of Cem
was dumped at 3695'. Shot off and pulled 6 5/8"
Casing After Casing was free we mudded hole
with 15 st of fresh fill mud. Laid down pipe
set rock bridge at 300' mixed and run 20 SX of Cem
mudded to 35' r. bridge and 10 SX Cem. to surface.

1-16-54

PLUGGING
FILE SEC 26 T 19 R 16W
BOOK PAGE 6 LINE 3

Warren H. Horner
District Conservation Agent

Date 1-13-54