

KANSAS

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 5 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
5-5-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Specter Pipe & Supply, Inc.

Complete Address Box 169, Russell, Kansas 67665

Lease Name Schafer Well No. 1

Location NE SE SW Sec. 5 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 3387'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Ralph Lynch Casing Pulling Co.

Address R. R. #4, Great Bend, Kansas License No. 457

Operation Completed: Hour Noon Day 3 Month ~~April~~ MAY Year 1972

The above well was plugged as follows:

5 1/2" plug pushed to 2925'. Hole filled with sand to 2900' and hole cemented with 5  
sacks cement. Rock bridge set from 200' to 190' and 5 sacks cement dumped on bridge  
and left to set up. Hole bailed dry and cemented with 20 sacks (total 25 sacks).  
Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to  
base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Alfred J. Swan*  
Well Plugging Supervisor

DATE 5/8/72  
INV. NO. 5689-W