

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.113.30243.0001

API NUMBER drilled 1938

LEASE NAME Goering

WELL NUMBER 7

2310 Ft. from S Section Line

1610 Ft. from ^W Section Line

SEC 29 TWP. 21 RGE. 1 ~~W~~ or (W)

COUNTY McPherson

Date Well Completed 5/3/38

Plugging Commenced 2/23/95

Plugging Completed 2/28/95

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009, McPherson, KS 67460

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/23/95 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? yes

Producing Formation Mississippi Depth to Top 2905 Ft. Bottom 2911 T.D. 3305 Ft.

PB 2916 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface Production		158'	0'	10"	158'	None
		3252'	0'	7"	3252'	413'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
(Bridgeplug @ 2916', perf. @ 2905'-2911'.) Ran 10 sacks cement for bottom plug 2916'-2856'. Pulled 413' of 7" casing, built bridge @ 380', and cemented to surface with 7 yards (161 sacks) 60/40 pozmix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hess Oil Company License No. 5663

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hess Oil Company

STATE OF KANSAS COUNTY OF MCPHERSON, ss.

Dick Hess

(Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dick Hess

(Address) same

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 95

My Commission Expires:



Notary Public