



15.113.20686.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

November 17, 1979

RECEIVED
CONSERVATION COMMISSION

NOV 21 1979

CONSERVATION DIVISION
Wichita, Kansas

11-21-79

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackston Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: Gould Oil, Inc.

Complete Address: 260 N. Rock Road, Suite 210, Wichita, Kansas

Lease Name: Rupp Well No. 1

Location: NW NW NE Sec. 25 Twp. 21 Rge. 2 (E) (W) X

County: McPherson Total Depth 3384' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Brucker was instructed to plug the well as follows:

8 3/8" 154' cem. circ. Fill hole with mud to 150'. Push
plug and 1/2 sack hulls to 150' and cement hole with
25 sacks cement. Fill hole with mud to 40'. Push plug
and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.
Bridge rat hole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent