



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 14 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Pulley of Dean & Clark has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Dean & Clark Inc.

Complete Address: Suite 20 400 N. Woodlawn, Wichita, Kansas

Lease Name: Holtsberg Well No. 1

Location: C NW SE Sec. 23 Twp. 21 Rge. 23 ^{XX} (E) (W)

County: Hodgeman Total Depth 4600' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

8 5/8" to 217' circulated w/ cement. 4 1/2" to 4600' cemented.

Top perforations 4497' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4400' Mud 4400' to 900'

Spot 80 sacks cement. 900' to 600' Mud 600' to 220'

Spot 30 sacks cement 220' to 120' Mud 120' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edna J. Lewis
 Conservation Division Agent